

YURT PLATFORM MATERIAL TAKEOFF

12-2x4-8' PT SLEEPER JOISTS
2-2x4-12' PT SLEEPER JOISTS
51 LIN. FT. $\frac{3}{8}$ "x5" PLYWOOD STRIP
(INCLUDED WITH YURT)
101 LIN. FT. $\frac{3}{4}$ "x1 $\frac{1}{2}$ " PLYWOOD STRIP
8 SHEETS $\frac{3}{4}$ "x4'x8' PLYWOOD SUBFLOOR


NOTE:
DEPENDING ON GRADE,
ENGINEERING REQUIREMENTS &
LOCAL CODES, FOUNDATION
BRACES MAY BE REQUIRED-
BRACES NOT SHOWN

MAIN DECK MATERIAL TAKEOFF

10-2x8-10' PT FLOOR JOISTS
9-2x8-8' PT BLOCKING
20 2x8 JOIST HANGERS
337 SQ. FT. (809 LIN. FT.) OF 1x6 PT
DECKING (ALLOWS FOR 20%
WASTE)

FOUNDATION MATERIAL TAKEOFF

9-12" DIAMETER CONCRETE
SONOTUBE PIERS
9-6x6 PT POSTS (LENGTH TO BE
DETERMINED BY GRADE)
9-SIMPSON ABE66 POST
ANCHORS
3-SIMPSON BCS2-3/6 POST CAPS
16- $\frac{3}{8}$ "x8" HOT DIPPED GALV.
CARRIAGE BOLTS, WASHERS, &
NUTS
14-2x12-10' PT GIRDER JOISTS
4-2x12-10' PT RIM JOISTS



4 Material Takeoff

SCALE NTS



16' Yurt Platform
Material Takeoff

369 Parkway Lane South
Floyd, VA 24091
540.745.7458
blueridgeyurts.com

SHEET NUMBER
16'-4